

August 26, 2009

City of Portsmouth, New Hampshire  
Addendum #3  
Bid #11-10

**Bow- Ceres Street Waterfront Improvements  
Clarification to item Add-Alt#2**

To the attention of all vendors submitting bids for this project.

This Addendum is a clarification to item Add-Alt #2, and forms part of the original bid document marked Bid #11-10 Bow – Ceres Street Waterfront Improvements.

Components to be included under this bid item:

Contractor shall furnish and install a complete turn-key concrete fence system as supplied by Acoustical Solutions, 2420 Grenoble Road, Richmond, VA 23294. Contact: Josh Oliber at 800-782-5742 x 32.

The concrete fence system will be used to create the 10' height x 17' long x 17' wide trash enclosure shown on sheet DT-11 of the contract drawings. Components of the system will include:

- 2 end posts
- 2 90 degree corner posts
- 9 line posts
- 60 Linear Feet of - 4' high x 5' long wood clapboard panels (2" thick)(These will need to be cut to fit for length for assembly)
- 60 Linear Feet of - 2' high x 5' long wood clapboard panels (2" thick)(These will need to be cut to fit for length for assembly)

Note: panels and posts shall have integral color which will be selected by the Owner's Representative through the submittal process

In addition to the concrete fence system, the contractor shall also include in his bid the following:

- a. Reinforced concrete pad with bond beam as shown on the drawings.
- b. A 4' high by 17.5" thick parapet wall for three sides of the 17' x 17' enclosure, cast in place with granite block form liner including all reinforcement. The wall will be used for the first 4' of the enclosure and will embed the 13 concrete fence posts. The concrete shall be mixed with integral color as manufactured by L. M. Scofield Company, 280 Park Ave., Rutherford, NJ 07070, Phone: (800) 800-9900 or approved equal. Color to be selected by Owner's Representative through the submittal process.
- c. Fenced gates as shown on detail sheet DT-8 as detail 4.
- d. Any other work specifically required to construct the enclosure completely.

Please acknowledge receipt of this addendum within your proposal, failure to do so may subject a bidder to disqualification.

End of Addendum #3